# CIRCULARION CONTRACT SUPPORT OF STRACT BY THE DESIRE

FABRICATION AND EVALUATION OF A CRYOSTABLE Nb<sub>2</sub>Sn SUPERCONDUCTOR FOR THE MIRROR FUSION TEST FACILITY (MFTF-B)

R. M. SCANLAN, J. P. ZBASNIK, R. W. BALDI, J. L. PICKERING, Y. FURUTO, M. IKEDA, S. MEGURO

1984 APPLIED SUPERCONDUCTIVITY CONFERENCE IEEE
SAN DIEGO, CA
September 9 - 13, 1984

September 1984

This is a preprint of a paper intended for publication in a journal or proceedings. Since changes may be made before publication, this preprint is made available with the understanding that it will not be cited or reproduced without the permission of the author.

#### DISCLAIMER

This document was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor the University of California nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial products, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government thereof, and shall not be used for advertising or product endorsement purposes.

FABRICATION AND EVALUATION OF A CRYOSTABLE Nb3Sn SUPERCONDUCTOR FOR THE MIRROR FUSION TEST FACILITY (MFTF-B)

R. M. Scanlan, J. P. Zbasnik
Lawrence Livermore National Laboratory
P.O. 5511 L-635.
Livermore, California 94550
R. W. Baldi, J. L. Pickering,
General Dynamics/Convair
P.O. 85377
San Diego, California 92138
Y. Furuto, M. Ikeda, and S. Meguro,
Furukawa Electric Co., Ltd.
Tokyo, 100, Japan

## Summary

The MFTF-B magnet system requires two 12.5T, 36 cm bore, insert coils. These coils are being constructed with a cryostable Nb<sub>3</sub>Sn conductor manufactured by Furukawa Electric Co. The conductor consists of a core soldered into a cold-worked copper housing, which provides strength. The Nb<sub>3</sub>Sn core is made by a triple extrusion bronze process. A total of 57 lengths, each 295 m long, have been made and tested. We have made extensive tests on this conductor; these tests include critical current, ambient and 4.2 K mechanical property measurements, critical current as a function of tensile strain, and bending tolerance tests. The critical current density was found to be quite anisotropic in this conductor, with  $J_{\rm c}(12{\rm T})=650{\rm A/mm}^2$  for field perpendicular to the conductor wide face, and  $J_{\rm c}(12{\rm T})=500{\rm A/mm}^2$  for field parallel to the conductor wide face. These values of current density are among the highest reported for a production lot of Nb<sub>3</sub>Sn conductor.

#### Introduction

This paper will describe the fabrication and evaluation of prototype and production lengths of a cryostable Nb<sub>3</sub>Sn superconductor for use in the Mirror Fusion Test Facility. The design of these coils (referred to as axicell coils) and the conductor have been discussed previously. The coils produce a central field (with background) of 12.0 T in a clear bore of 36 cm. Two coils are required for MFTF-B; each coil consists of 27 double pancakes and hence a total of 54 double pancake lengths, each 295 m long, are required. The operating current is 1500 A, and the maximum field at the conductor is 12.52 T.

The initial design for MFTF-B employed a different coil configuration which utilized all NbTi conductor. Subsequent analysis showed that improved operation could be achieved with the high field axicell design. However, the implementation of this major change, without appreciable delay in the project completion date, meant that the Nb<sub>3</sub>Sn conductor procurement must be rapid and that the vendor must deliver conductor on a tight schedule (first conductor delivery 12 months after receipt of the order).

## **Conductor Manufacture**

Furukawa Electric Co., Ltd. was awarded a fixed-price contract to manufacture this conductor. A major technical factor in the choice of Furukawa was their experience in fabricating conductor for the Cluster Background Coils (CBC) at JAERI. The CBC and MFTF-B conductors are similar in that they both consist of a reacted Nb $_3$ Sn core soldered into a cold-worked copper housing. Also, both the CBC and the MFTF-B cores are fabricated using the Furukawa version of the bronze process. A major difference between the two conductors is that the CBC conductor was designed for 10 T operation, whereas the MFTF-B coil operates at 12.5 T. Several problems, including degradation of the  $\rm I_C$  due to strain and anisotropy in  $\rm I_C$ , are more severe in the higher field MFTF-B application. In addition, the Lorentz forces acting upon the conductor are considerably higher. These effects will be discussed in the section on Test Results.

Fabrication was initiated on a pre-prototype length in order to gain manufacturing experience while the new materials (Nb and bronze) were being assembled. The Nb used in this pre-prototype length was not of high quality, and it produced filaments which were non-uniform in cross-section. This problem has occurred in other Nb<sub>3</sub>Sn composites. several important observations were made on this pre-prototype which were incorporated into the prototype design: a) The anisotropy in critical current (see Test Results section for an explanation) was somewhat higher than anticipated, and to compensate for this the Nb<sub>3</sub>Sn volume fraction was increased; b) during billet extrusion, some nonuniform deformation occurred near the diffusion barrier requiring an improvement in the third stage billet stacking; c) some Nb<sub>3</sub>Sn formation was observed to occur during the bronze annealing, so the annealing temperature was adjusted. The fabrication steps for the prototype length and the 56 production lengths will now be discussed.

In order to avoid production problems previously reported for bronze process conductors  $^{3,4}$  the Nb, Cu, and bronze raw materials were carefully specified and prepared. The Nb rods, obtained from Teledyne Wah Chang Albany (TWCA) were specified with respect to chemistry, grain size, hardness, surface condition, and freedom from porosity. The bronze composition is  $14.3 \pm 0.5$  wt % Sn,  $0.23 \pm .05$  wt % Ti, balance Cu; the bronze to Nb ratio is maintained between 2.6:1 and 3.2:1. The copper has an initial RRR greater than 200 and a purity greater than 99.99%.

The multifilamentary composite is fabricated in three extrusion steps, with intermediate cold drawing steps. The first extrusion consists of a Nb rod in a bronze pipe; after extrusion and drawing, lengths of this material are loaded into a second billet (380 Nb cores), extruded and drawn. The final extrusion billet consists of approximately 380 second extrusion cores inside a Nb diffusion barrier and a copper can. This extrusion is drawn and then aspected to produce the superconductor core 2.11 mm by 6.91 mm in cross-section. Reaction of these lengths to form the Nb<sub>3</sub>Sn is performed at 700° C for several days in an inert atmosphere. Three lengths 300 m each are heat-treated simultaneously on a set of nested mandrels 600, 700, and 800 mm in diameter. The mandrels are stainless steel with spiral machined grooves to prevent the turns from touching and bonding during heat treatment. The diameters of the mandrels are chosen to minimize the amount of strain the Nb<sub>3</sub>Sn filaments will experience during subsequent processing and coil winding. 1

Throughout the processing, quality control is maintained by checks on (a) cracks or other flaws in the bronze, (b) dimensions, (c) bronze:Nb ratio, (d) uniformity of composite cross-section. In addition, eddy current detection is performed on the composite during processing to find inclusions and to monitor the copper to non-copper ratio.

Finally, the superconductor core is clad with cold-worked Cu for additional strength and to provide cryostability. The cladding consists of a channel piece and a "hat" which are soldered onto the core (Fig. 1) with 60 Sn, 40 Pb solder. The outside surfaces of the Cu cladding are coated with copper oxide so that the solder does not wet these surfaces. The quality of solder bond is monitored ultrasonically, and no completely unbonded zone on both wide faces greater than 0.5 cm is permitted. In addition, no more than 20% of total bondable area in any 10 cm length may be unbonded.

The soldering line is designed so that the strain on the reacted Nb<sub>3</sub>Sn core is minimized. This is accomplished by a straight-through line design, a moving core payoff, and large diameter rolls and guides. The copper cladding is protected from annealing by careful control of solder bath temperature and a fast-drain system, which can be activated in the event of a power failure. Only three lengths out of a total of 60 lengths produced were out of specification with respect to solder bond quality. The dimensional specification on the completed conductor is 5.21± .1 mm by 11.00± .1 mm; actual extrema are 5.226 mm to 5.163 mm on the thickness and 11.00 mm to 11.06 mm on the width. The fabrication of the required 57 lengths (54 needed, plus two spare lengths and the prototype length) were completed on schedule with no major problems. Early in the production period, some bronze pipes were found to have cracks, but they were replaced without a serious delay in production. The processing of raw material for production lengths began in August 1983, and the final length was ready for shipment by June 15, 1984.

### Test Results

The coil design requires this conductor to withstand substantial straining during construction and operation; hence a comprehensive series of tests were performed on the prototype length in order to assess the affect of strain on critical currents. These tests were designed to provide engineering data for this particular coil; however, the empirical scaling relationships developed by Ekin<sup>5</sup> can be used to interpret the results.

The first test was designed to evaluate the strain sensitivity of the Nb $_3$ Sn superconductor insert, since this insert is processed through the cladding line after reaction to form Nb $_3$ Sn. The insert was reacted in four configurations (straight, R = 40 cm, 20 cm and 10 cm). The curved reacted specimens were straightened and all specimens tested. The results, as shown in Figure 2 indicated an enhancement in current carrying capability at the operating strain condition (approximately .002 bending strain). The bending strain induced into the specimens (from straightening) did not show any I $_c$  degradation (from the straight specimens) up to .0048 bending strain. The relatively small I $_c$  enhancement due to bending strain can be attributed to a minor neutral axis shift effect.

Another test involved the evaluation of the tolerance due to bending of the completed conductor, including the copper cladding. Conductors with inserts reacted on a 70 cm diameter were bent both in the "right direction" (decreasing reaction diameter) and in the "wrong direction" (opposite direction from the reacted shape), thus producing a bending strain in the insert. The measurements again showed (Fig. 3) an increase in  $I_{\rm C}$  up to a bending strain condition of approximately 0.008 (for both the right and wrong way bending) which has been defined as  $E_{\rm IRREV}$ . The  $E_{\rm IRREV}$  = 0.008 was used to develop minimum radius conditions for a right/wrong way bending tolerance that could be used during fabrication of the magnet.

The  $I_{\rm C}$  vs. bending results in both the insert and conductor illustrated an increase in current carrying capability before degradation begins (Figures 2 and 3). This increase in  $I_{\rm C}$  vs. bending strain has been attributed to a neutral axis shift in the conductor. Since the neutral axis shift has the potential of increasing the strain in the conductor, an analytical technique was developed to estimate this strain .

Typical  $Nb_3Sn$  conductor current carrying characteristics are shown schematically with respect to intrinsic strain ( $Nb_3Sn$  fiber uniaxial strain) in Fig. 4 as shown. The curve can be represented by an empirically-developed equation. The constants used to represent the typical  $Nb_3Sn$  characteristics are taken as B = 12.5T and T = 4.2K. The effect of bending strain on the critical current can be estimated by integrating within the limits of the applied bending strain.

The state of prestrain ( $\epsilon_i$ ) in the matrix is important in considering the bending strain effects because it influences the position of the neutral axis during bending. To obtain the critical current of the bent conductor  $J_c(\epsilon)$  is integrated over the different tensile and compressive regions of the conductor (averaging over the uniaxial strain curve). The changes in  $J_c$  without a shift in the neutral axis are nearly symmetrical about point A (Figure 4) and the net changes in  $J_c$  will be slight.

A large prestress shifts the neutral axis from the center of the conductor toward the center of curvature during bending. Under this condition, the changes in  $J_C$  (about point A) will no longer be symmetrical. A larger portion of the superconductor will experience an applied tensile strain and the net  $J_C$  value will, therefore, increase initially during bending. By knowing the amount of  $J_C$  increase and the initial prestress of the matrix (both developed from tests), an estimate of the additional strain (over the simple bending relationship, E = d/D) due to the neutral axis shift can be developed. The conclusion from this analysis is that a neutral axis shift does occur, but the effect is small, leading to an additional strain of .05% compared with the maximum strain of 0.2% calculated for handling this conductor.

A similar Nb $_3$ Sn conductor clad with cold- worked Cu had shown a significant reduction in I $_c$  due to cladding $^6$ . This effect was evaluated for the present conductor and found to be only 6-10%.

A number of routine measurements were made on the production lengths in order to evaluate reproducibility. Each final extrusion produced three lengths at final size, so a sampling plan was devised so that samples were taken from each end of these three lengths but duplicates were eliminated. Samples were taken after cladding and critical current measurements were made on straight samples in a 13 T split solenoid with a field uniformity of  $\pm 1\%$ over a 5 cm length. Critical current measurements on a large cross section monolith such as this are difficult due to the long current transfer distance arising from current transfer across the resistive bronze matrix. The spacing between voltage taps was reduced to 1 cm in order to reduce the contribution of this current transfer voltage, and then this contribution was removed by constructing a new base line. A criterion of P =  $10^{-11}$   $\Omega$  -cm was then used to define the critical current. Several samples of prototype material were measured first with the field perpendicular to the conductor wide face and then parallel to the wide face. These measurements showed a rather large degree of anisotropy, with the  $I_{\rm C}$  (perpendicular) being about 25% higher than  $I_{\rm C}$  (parallel). This effect has been observed in other highly aspected conductors  $^8$  and experiments are in progress to understand this effect. 9 In the MFTF-B coil design the field is parallel to the wide face, so that  $I_c$  (parallel) is the applicable value and  $I_c$ (parallel) was measured for all production lengths.

Critical current measurements were made in a total of 80 samples from the production lengths. The average value is  $I_{\rm C}$  = 5200 A at 12.0 T and  $I_{\rm C}$  = 4600 A at 12.5 T and all values are within 11% of the average. All samples greatly exceeded the specification value of 3400 A at 12.5 T. The average critical current value  $I_{\rm C}$  = 5200 A corresponds to a critical current density in the non-copper area  $J_{\rm C}$  (12 T) = 520 A/mm<sup>2</sup>. These values are among the highest yet reported for a production order of this size.

# Conclusions:

- The bronze process with a Ti-doped, high-Sn-content has been used successfully to fabricate a large quantity (17,000 m) of cryostable Nb<sub>3</sub>Sn superconductor.
- 2. The results of bend tests and other mechanical property tests indicate that this reacted  $Nb_3Sn$  conductor is capable of withstanding the handling and Lorentz forces anticipated in the MFTF-B axicell coils.

The authors would like to acknowledge the contributions of their colleagues at LLNL\*, General Dynamics/Convair, and Furukawa Electric who have contributed to this project. Steve Mance and Rick Gross of LLNL performed the important yet tedious task of measuring the critical currents of approximately 100 samples. As MFTF Magnet Program Leader, Ted Kozman has provided continuous encouragement and support.

\*This work was performed under the auspices of the U.S. Department of Energy by Lawrence Livermore National Laboratory under contract No. W-7405-Eng-48.

## References

- R.W. Baldi, R.E. Tatro, K.L. Agarwal, R.E. Bailey, W.F. Baxter, J.E. Burgeson, I.K. Kim, A.J. Ritschel, Adv. in Cryogenic Engineering 29, 67-78 (1984)
- 2. Y. Furuto, Y. Tanaka, S. Meguro, T. Suzuki, and I. Inoue, Ninth Symposium on the Eng. Problems of Fusion Res., IEEE Pub. No. 81CH1715-2, p. 330-334 (1981)
- 3. R.M. Scanlan, D. N. Cornish, C.R. Spencer, E. Gregory and E. Adam, IBID, p 1318
- 4. D.B. Smathers, K.R. Marken, D.C. Larbalestier, and R.M. Scanlan, IEEE trans. on Magnetics MAG-19 p. 1417-1420 (1983)
- 5. J.W. Ekin, <u>Superconducting Materials Science: Metallurgy Fabrication and Applications</u>, S. Foner and B. Schwartz, Eds., Plenum Press, p. 455-510 (1981)
- 6. Y. Furuto, private communication
- 7. J.W. Ekin, J. Appl. Phys. 49(6), 3406-3409 (1978)
- 8. K. Kamata, N. Iada, K. Iton, and K. Tachikawa, Advances in Cryogenic Engineering 30, 771-778 (1984)
- 9. M. Suenaga, Paper NMI, these proceedings




Fig. la Cross-section of the conductor showing the cold-worked Cu cladding (U-shaped channel and "hat") with insert soldered in place.




Fig. 1b Enlarged section of the insert showing outer copper, Nb diffusion barrier and Nb<sub>3</sub>Sn in bronze matrix.




Fig. 2 Effect of bending strain on critical current for samples of the conductor insert.




Fig. 3 Effect of bending strain on the critical current of the current of the assembled conductor (insert and Cu cladding).

#### USING DEVELOPED SCALING LAWS (EKIN)




Fig. 4 Schematic diagram illustrating the effects of bending strain on the critical current.